

2. AMENDMENT/MODIFICATION NO. 0004	3. EFFECTIVE DATE APR 20, 2004	4. REQUISITION/PURCHASE REQ. NO. N/A	5. PROJECT NO. (If applicable) SPEC. NO. 1401
6. ISSUED BY CODE		7. ADMINISTERED BY (If other than Item 6) CODE	
DEPARTMENT OF THE ARMY U.S. ARMY ENGINEER DISTRICT, SACRAMENTO SACRAMENTO, CALIFORNIA 95814-2922		DEPARTMENT OF THE ARMY U.S. ARMY ENGINEER DISTRICT, SACRAMENTO SACRAMENTO, CALIFORNIA 95814-2922	

8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)	(✓)	9A. AMENDMENT OF SOLICITATION NO. W91238-04-R-0012
	X	9B. DATED (SEE ITEM 11) MAR 05, 2004
		10A. MODIFICATION OF CONTRACTS/ORDER NO. N/A
		10B. DATED (SEE ITEM 13) N/A
CODE	FACILITY CODE	

**11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers  is extended,  is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)  
N/A

NOTE: ITEM 13 BELOW IS N/A.

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

(✓)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A. N/A
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority) N/A

**E. IMPORTANT:** Contractor  is not,  is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)  
Competitive 8(a) Multiple Award Task Order Contract  
California Boundaries of the Sacramento District Corps of Engineers, and Hawthorne Army Depot, Nevada

1 Encl  
1. Revised Pages: 01012-6, 13280-5

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)	16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)
15B. CONTRACTOR/OFFEROR  (Signature of person authorized to sign)	15C. DATE SIGNED
	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)
	16C. DATE SIGNED

SAMPLE PROJECT

in the CSTR column).

2.5.3 As-Built Drawings shall be provided as per the requirements of Section 01330 of the Technical Specifications included in this solicitation.

**3. TRANSMITTAL TO GOVERNMENT AGENCIES:**

3.1 Government agencies shall receive copies of the Work Plan and Color Board in the quantities indicated below (Note: CSTR stands for "construction"). Originals of transmittal letters should be sent to the Valley Resident Office (ATTN: Ralph Cameron) and copies should accompany each mail package. Transmittal letters shall indicate distribution by use of the "ATTN" code shown in the address.

<u>ACTIVITY ADDRESS</u>	<u>Work Plan</u>		<u>Color Board</u>	
	<u>100%</u>	<u>CSTR</u>	<u>100%</u>	<u>CSTR</u>
US ARMY ENGINEER DISTRICT, SACRAMENTO ATTN: CESP-K-PM-M, (Project Manager: Greg Bridgestock) 1325 J. STREET SACRAMENTO, CA. 95814-2922 Phone: (916) 557-5127	5	5	1	1
US ARMY CORPS OF ENGINEERS ATTN: Monterey Project Office (Steven Scholten) 2850 5 <sup>th</sup> Avenue Marina, CA 93933 Phone: (831) 884-9925 x223	3	3	1	1
Defense Language Institute & Presidio of Monterey	1	1	2	2
<b>Overnight Mail:</b> Directorate of Public Works ATTN: Tony Barcinas Building 4455 Gigling Road Ord Military Community Seaside, CA 93955 Phone:(831) 242-7779				
<b>Regular Mail:</b> <b>Defense Language Institute</b> <b>ATZP-DPW</b> <b>Bldg 4455 (OMC)</b> <b>Presidio of Monterey, CA 93944</b>				
U.S. Army Corps of Engineers Valley Resident Office ATTN: CESP-K-CO-RV (Ralph Cameron) 2021 Jefferson Blvd West Sacramento, CA 95691-0935 Phone: (916) 373-1617 ext. 321	1	1	0	0

**4. DAILY WORK SCHEDULES**

4.1 In order to closely coordinate work under this contract, the Contractor shall prepare for and attend a weekly coordination meeting with the Contracting Officer at which time the Contractor shall submit for coordination and approval, his/her proposed daily work schedule for the next two week period. Required temporary utility services, time and duration of interruptions, and protection of adjoining areas shall be included with the Contractor's proposed 2-week work schedule. At this meeting, the Contractor shall also submit his/her schedule of proposed dates and times of all preparatory inspections to be performed during the next 2 weeks. Coordination action by the Contracting Officer relative to these schedules will be accomplished during these weekly meetings.

4.2 The work hours for demolition and water shut downs shall be limited to 3:30pm-9:00pm on week days [target Fridays], and 7:00am-5:00pm on weekends. All

- jj. Thermal system insulation (TSI) ACM: ACM which contains more than 1% asbestos and is applied to pipes, fittings, boilers, breeching, tanks, ducts, or other interior structural components to prevent heat loss or gain or water condensation.
- kk. Transite: A generic name for asbestos cement wallboard and pipe.
- ll. Worker: Individual (not designated as the Competent Person or a supervisor) who performs asbestos work and has completed asbestos worker training required by 8 CCR Section 1529, to include EPA Model Accreditation Plan (MAP) "Worker" training; accreditation required by 40 CFR 763, Subpart E, Appendix C, if required by the OSHA Class of work to be performed or by the state where the work is to be performed.
- mm. Asbestos Containing Construction Material (ACCM): Any manufactured construction material, which contains more than one tenth of 1 percent asbestos by weight. (California)
- nn. Asbestos Consultant: Person who contracts to provide professional health and safety services relating to ACCM, which comprises 100 square feet or more of surface area. The activities of an asbestos consultant include building inspection, abatement project design, contract administration, sample collection preparation of asbestos management plans, clearance monitoring, and supervision of site surveillance technicians. (California)
- oo. Site Surveillance Technician: Person who acts as an independent on-site representative of an asbestos consultant who monitors the asbestos abatement activities and provides asbestos air monitoring services for area and personal samples. (California)

### 1.3 Description of Work

The work covered by this section includes the removal of asbestos-containing materials (ACM) which are encountered during renovation activities associated with this project and describes procedures and equipment required to protect workers and occupants of the regulated area from contact with airborne asbestos fibers and ACM dust and debris. Activities may include OSHA Class I, Class II, and Class III work operations involving ACM. Additionally, this section describes procedures/work practices for ACCM that is encountered during renovation activities. The work also includes containment, storage, transportation and disposal of the generated ACM/ACCM wastes. More specific operational procedures shall be detailed in the required APP/IIPP, the AHAP and AHAs required in paragraph SAFETY AND HEALTH PROGRAM AND PLANS. The Contractor shall consider that all toilet wax rings/seals, pipe wrap/lagging, *ceramic tile mastic*, and wallboard/joint compound materials contain ACM/ACCM.

#### 1.3.1 Unexpected Discovery of Asbestos

For any building components suspected to contain asbestos and located in areas impacted by the work, the Contractor shall notify the Contracting Officer (CO) who will have the option of ordering up to 10 bulk samples to be obtained at the Contractor's expense and delivered to a laboratory accredited under the National Institute of Standards and Technology (NIST) "National Voluntary Laboratory Accreditation Program (NVLAP)" and analyzed by PLM at no additional cost to the Government. If the asbestos content is less than 10 percent, as determined by a method other than point counting, the asbestos content shall be verified by point counting. Any additional components identified as ACM that have been approved by the Contracting Officer for removal shall be removed by the Contractor and will be paid for by an equitable adjustment to the contract price under the CONTRACT CLAUSE titled "changes". Sampling activities undertaken to determine the presence of additional ACM/ACCM shall be conducted by personnel who have successfully completed the EPA Model Accreditation Plan (MAP) "Building Inspector" training course required by 40 CFR 763, Subpart E, Appendix C and who are California Certified Asbestos Consultant or Certified Site Surveillance Technician..

### 1.4 Submittals

Government approval is required for submittals with a "G" designation; the USACE Resident Engineer (RE) will review the submittals for the Government. Submittals not having a "G" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data