

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE N/A		PAGE 1 OF 27 PAGES	
2. AMENDMENT/MODIFICATION NO. 0019		3. EFFECTIVE DATE 2 JUL 2003		4. REQUISITION/PURCHASE REQ. NO. N/A		5. PROJECT NO. (If applicable) SPEC. NO. 1296	
6. ISSUED BY DEPARTMENT OF THE ARMY U.S. ARMY ENGINEER DISTRICT, SACRAMENTO SACRAMENTO, CALIFORNIA 95814-2922		CODE		7. ADMINISTERED BY (If other than Item 6) SEE ITEM 6		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(✓)		9A. AMENDMENT OF SOLICITATION NO. DACW05-03-B-0007	
				✗		9B. DATED (SEE ITEM 11) N/A	
				✗		10A. MODIFICATION OF CONTRACTS/ORDER NO. N/A	
						10B. DATED (SEE ITEM 13) N/A	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.							
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required) N/A							
NOTE: ITEM 13 BELOW IS N/A.							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
(✓) A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A. N/A							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority) N/A							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) SACRAMENTO RIVER FLOOD CONTROL SYSTEM PHASE 11 - MARYSVILLE/YUBA AREA SITE 7 EXTENSION YUBA COUNTY, CALIFORNIA							
NOTE: THE BID OPENING TIME HAS BEEN CHANGED FROM: 1:00 P.M. TO 10:00 A.M.							
1 ENCL							
1. SF 1442, 00100, 02300 AND 02300A.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
_____ (Signature of person authorized to sign)				BY _____ (Signature of Contracting Officer)			
NSN 7540-01-152-8070 PREVIOUS EDITION UNUSABLE				30-105-02		STANDARD FORM 30 (REV. 10-83) Prescribed by GSA FAR (48 CFR) 53.243	
				USAPPC V2.00			

SOLICITATION, OFFER, AND AWARD <i>(Construction, Alteration, or Repair)</i>	1. SOLICITATION NO.	2. TYPE OF SOLICITATION	3. DATE ISSUED	PAGE
	DACW05-03-B-0007	<input checked="" type="checkbox"/> SEALED BID (IFB) <input type="checkbox"/> NEGOTIATED(RFP)	21-Apr-2003	1
IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.				
4. CONTRACT NO.	5. REQUISITION/PURCHASE REQUEST NO.		6. PROJECT NO.	
7. ISSUED BY CODE DEPARTMENT OF THE ARMY CORPS OF ENGINEERS, SACRAMENTO 1325 J STREET SACRAMENTO, CALIFORNIA 95814-2922 FAX: (916)557-5278		8. ADDRESS OFFER TO <i>(If Other Than Item 7)</i> CODE See Item 7 TEL: FAX: 		
9. FOR INFORMATION CALL:	A. NAME SHIRLEY A MARTIN		B. TELEPHONE NO. <i>(Include area code)</i> (NO COLLECT CALLS) 916-557-6902	
SOLICITATION				
NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".				
10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS <i>(Title, identifying no., date):</i> SACRAMENTO RIVER FLOOD CONTROL SYSTEM PHASE II - MARYSVILLE/YUBA AREA SITE 7 EXTENSION YUBA COUNTY, CALIFORNIA SPECIFICATION NO. 1296 DESCRIPTION: LEVEE REMEDIAL CONSTRUCTION AT FEATHER RIVER LEFT BANK FROM L.M. 11.03 TO L.M. 12.8 AND RELOCATED PUMPING STATION. NOTE: THIS PROCUREMENT IS RESTRICTED TO 8A FIRMS HAVING A VALID OFFICE GEOGRAPHICALLY LOCATED WITHIN THE SAN FRANCISCO SBA DISTRICT BOUNDARIES. THE BIDDERS ATTENTION IS DIRECTED TO SECTION 00100 IN THE SOLICITATION FOR INFORMATION REGARDING THE TOUR OF THE SITE. ESTIMATED COST RANGE OF PROJECT: \$5,000,000 - \$10,000,000				
11. The Contractor shall begin performance within <u>10</u> calendar days and complete it within <u>180</u> calendar days after receiving <input type="checkbox"/> award, <input checked="" type="checkbox"/> notice to proceed. This performance period is <input checked="" type="checkbox"/> mandatory, <input type="checkbox"/> negotiable. <i>(See FAR 52.211-10)</i>				
12 A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? <i>(If "YES," indicate within how many calendar days after award in Item 12B.)</i> <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO			12B. CALENDAR DAYS 5	
13. ADDITIONAL SOLICITATION REQUIREMENTS: A. Sealed offers in original and <u>0</u> copies to perform the work required are due at the place specified in Item 8 by 10:00 A.M. <i>(hour)</i> local time 8 JUL 2003 <i>(date)</i> . If this is a sealed bid solicitation, offers must be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due. B. An offer guarantee <input checked="" type="checkbox"/> is, <input type="checkbox"/> is not required. C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference. D. Offers providing less than <u>60</u> calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.				

SOLICITATION, OFFER, AND AWARD*(Construction, Alteration, or Repair)***OFFER (Must be fully completed by offeror)**

14. NAME AND ADDRESS OF OFFEROR <i>(Include ZIP Code)</i>		15. TELEPHONE NO. <i>(Include area code)</i>
		16. REMITTANCE ADDRESS <i>(Include only if different than Item 14)</i>
CODE	FACILITY CODE	

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. *(Insert any number equal to or greater than the minimum requirements stated in Item 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.)*

AMOUNTS	SEE SCHEDULE OF PRICES
---------	------------------------

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGMENT OF AMENDMENTS*(The offeror acknowledges receipt of amendments to the solicitation -- give number and date of each)*

AMENDMENT NO.										
DATE										

20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER <i>(Type or print)</i>	20B. SIGNATURE	20C. OFFER DATE
--	----------------	-----------------

AWARD (To be completed by Government)

21. ITEMS ACCEPTED:

22. AMOUNT	23. ACCOUNTING AND APPROPRIATION DATA
------------	---------------------------------------

24. SUBMIT INVOICES TO ADDRESS SHOWN IN <i>(4 copies unless otherwise specified)</i>	ITEM	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO <input type="checkbox"/> 10 U.S.C. 2304(c) <input type="checkbox"/> 41 U.S.C. 253(c)
---	------	--

26. ADMINISTERED BY	CODE	27. PAYMENT WILL BE MADE BY:	CODE
---------------------	------	------------------------------	------

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

<input type="checkbox"/> 28. NEGOTIATED AGREEMENT <i>(Contractor is required to sign this document and return _____ copies to issuing office.)</i> Contractor agrees to furnish and deliver all items or perform all work, requisitions identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications or incorporated by reference in or attached to this contract.	<input type="checkbox"/> 29. AWARD <i>(Contractor is not required to sign this document.)</i> Your offer on this solicitation, is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.
--	--

30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN <i>(Type or print)</i>		31A. NAME OF CONTRACTING OFFICER <i>(Type or print)</i>	
30B. SIGNATURE	30C. DATE	TEL: _____ EMAIL: _____	
		31B. UNITED STATES OF AMERICA BY	31C. AWARD DATE

Section 00100 - Bidding Schedule/Instructions to Bidders

52.0214-4581 INQUIRIES (NOV 2002)

Prospective bidders should submit inquiries related to this solicitation in accordance with the following (collect calls will not be accepted):

(1) For information related to ordering solicitation packages, amendments, the time and dates of bid openings, and for copies of the solicitation mailing list, please check our website at the following URL: <http://ebs.spk.usace.army.mil> If the site is temporarily unavailable, please FAX your inquiry to our Plan Room at (916) 557-7842

(2) For inquiries of a contractual nature (solicitation requirements, interpretation of contractual language):

Contract Specialist: Shirley Martin
Telephone: (916) 557-6902
FAX: (916) 557-5278

For bid results go to the Sacramento District, Contracting Division website <http://ebs.spk.usace.army.mil>. If this site has no bid information, call the Contract Specialist above.

(3) All technical questions on the specifications or drawings must be submitted in writing using one of the following:

MAILING ADDRESS:

Department of the Army
U.S. Army Engineer District, Sacramento
Contracting Division (Attn: Shirley Martin)
1325 J Street
Sacramento CA 95814-2922

FAX: (916) 557-7854, Attn: Shirley Martin

E-MAIL: Shirley.A.Martin@usace.army.mil AND Ronald.A.Schunk@usace.army.mil.

(4) Please include the solicitation number, the project title, the location of the project, the full name of your company and your telephone and FAX numbers in your correspondence. Written inquiries should be received by this office not later than 14 calendar days prior to the date set for bid opening.

(5) Oral explanations or instructions are not binding. Changes to the solicitation can only be made by an amendment to the solicitation.

52.0214-4582 DIRECTIONS FOR SUBMITTING BIDS (MAR 2003)

Envelopes containing bids must be sealed, marked and addressed as follows:

MARK ENVELOPES:

Solicitation No. DACW05-03-B-0007
Bid Opening Date: 8 **JULY 2003**
Bid Opening Time: 10:00 AM Local Time

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02300

EARTHWORK (LEVEE)

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 MEASUREMENT
 - 1.2.1 Excavation, Fill, and Borrow
 - 1.2.1 Topsoil Requirements
- 1.3 PAYMENT
- 1.4 DEFINITIONS
 - 1.4.1 Satisfactory Materials
 - 1.4.1.1 General Earthwork Material
 - 1.4.1.2 Levee Reconstruction Material
 - 1.4.2 Unsatisfactory Materials
 - 1.4.2.1 Unstable Material
 - 1.4.3 Degree of Compaction
- 1.5 SUBMITTALS
- 1.6 SUBSURFACE DATA
- 1.7 CLASSIFICATION OF EXCAVATION
- 1.8 BLASTING
- 1.9 UTILIZATION OF EXCAVATED MATERIALS

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 STRIPPING OF TOPSOIL
- 3.2 GENERAL EXCAVATION
 - 3.2.1 Channels
 - 3.2.2 Drainage Structures
- 3.3 SELECTION OF BORROW MATERIAL
- 3.4 OPENING AND DRAINAGE OF EXCAVATION AND BORROW PITS
- 3.5 BACKFILL
- 3.6 PREPARATION OF GROUND SURFACE FOR EMBANKMENTS
 - 3.6.1 General Requirements
- 3.7 EMBANKMENTS
 - 3.7.1 Levee Reconstruction
 - 3.7.2 General Earthwork
- 3.8 SUBGRADES
 - 3.8.1 Construction
 - 3.8.2 Compaction
- 3.9 FINISHING
- 3.10 TESTING
 - 3.10.1 Fill and Backfill Material Gradation

- 3.10.2 In-Place Densities
- 3.10.3 Check Tests on In-Place Densities
- 3.10.4 Moisture Contents
- 3.10.5 Optimum Moisture and Laboratory Maximum Density
- 3.10.6 Tolerance Tests for Subgrades
- 3.11 SUBGRADE AND EMBANKMENT PROTECTION

-- End of Section Table of Contents --

SECTION 02300

EARTHWORK(LEVEE)

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
(AASHTO)

AASHTO T 180 (1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop

AASHTO T 224 (1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136 (1996a) Sieve Analysis of Fine and Coarse Aggregates

ASTM D 422 (1963; R 1998) Particle-Size Analysis of Soils

ASTM D 1556 (1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method

ASTM D 1557 (1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))

ASTM D 2487 (1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)

ASTM D 2922 (1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)

ASTM D 3017 (1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

ASTM D 4318

(1998) Liquid Limit, Plastic Limit, and
Plasticity Index of Soils

1.2 MEASUREMENT

1.2.1 Excavation, Fill, and Borrow

The unit of measurement for excavation, fill, will be the cubic yard, computed by the average end area method from cross sections taken before and after the excavation, fill, operations. The volume to be paid for will be the number of cubic yards of material measured in its original position and removed from the excavation areas, including the excavation for underground conduits and channels, when the material is acceptably utilized or disposed of as herein specified. The measurements will include authorized excavation of concrete slabs and debris, and the authorized excavation and disposal of unsatisfactory materials; allowance will be made on the same basis for satisfactory material ordered as replacement. The measurement will not include the volume of subgrade material or other material that is scarified or plowed and reused in-place, and will not include the volume excavated without authorization or the volume of any material used for purposes other than directed. The measurement will not include the volume of any excavation performed prior to the taking of elevations and measurements of the undisturbed grade.

1.2.1 Topsoil Requirements

Surface excavation, hauling, and spreading or piling of topsoil and related miscellaneous operations will be considered subsidiary obligations of the Contractor, covered under the contract unit price for general earthwork and levee reconstruction.

1.3 PAYMENT

Payment will constitute full compensation for all labor, equipment, tools, supplies, and incidentals necessary to complete the work for excavation, fill and backfill, for the Line Items:

1. "GENERAL EARTHWORK" which includes excavation of the levee section, and the proper land side placement and compaction of locally excavated "satisfactory" materials.

2. "LEVEE RECONSTRUCTION" which includes levee reconstruction with properly placed and compacted locally excavated "satisfactory" materials.

3. "BORROW" which includes the import and proper placement and compaction of materials specified herein as "satisfactory" for either general earthwork or levee reconstruction. .

1.4 DEFINITIONS

1.4.1 Satisfactory Materials

1.4.1.1 General Earthwork Material

Satisfactory materials for general earthwork and stability berm and seepage berm construction shall comprise any materials classified by ASTM D 2487 as GC, GP-GC, GM-GC, SC, SW-SC, SP-SC, and CL. Satisfactory materials for general earthwork shall have a particle size of less than 2 inches in any dimension. The fines portion of general earthwork material shall have a liquid limit of no greater than 45 when tested in accordance with ASTM D 4318. Material for the drainage layer is specified in Section 02714A DRAINAGE LAYER.

1.4.1.2 Levee Reconstruction Material

Satisfactory materials for reconstruction within the prismatic section of the excavated levee shall comprise materials classified by ASTM D 2487 as GC and SC. The fines portion of levee reconstruction material shall have a liquid limit of no greater than 35 when tested in accordance with ASTM D 4318. Satisfactory materials for levee reconstruction shall have a particle size of less than 2 inches in any dimension.

1.4.2 Unsatisfactory Materials

Materials which do not comply with the requirements specified for satisfactory materials for general earthwork, levee reconstruction, and bridging materials are unsatisfactory. Unsatisfactory materials also include man-made fills; trash; refuse; backfills from previous construction compacted to lesser densities than specified herein; material classified as satisfactory which contains root and other organic matter; and unstable material. The Contracting Officer shall be notified of any contaminated materials.

1.4.2.1 Unstable Material

Unstable material is material too wet to be compacted to the densities specified herein, material that will not support construction equipment, and material that rutts or shoves under the wheels of construction equipment, imprints when walked upon, or pierces when probed with a number-4 reinforcing bar. The Contractor is advised that unstable material is likely to exist on the construction site and no additional compensation shall be forthcoming for disk-drying operations, bridging operations, or chemical stabilization.

1.4.3 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum dry density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 3/4 inch sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 3/4 inch sieve shall be expressed as a percentage of the maximum density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Earthwork; G, RE.

Procedure and location for disposal of unused satisfactory material. Proposed source of borrow material. Initial classification test results for general earthwork materials and levee reconstruction materials. **No materials are to be delivered to the site or placed as fill or backfill without testing and authorization from the Contracting Officer.**

Advance notice on the opening of excavation or borrow areas.

SD-06 Test Reports

Testing;

Within 24 hours of conclusion of physical tests, 2 copies of test results, including calibration curves and results of calibration tests.

SD-07 Certificates

Testing;

Qualifications of the commercial testing laboratory or Contractor's testing facilities.

1.6 SUBSURFACE DATA

Subsurface soil boring logs are shown on the drawings. These data represent the best subsurface information available; however, variations may exist in the subsurface between boring locations.

1.7 CLASSIFICATION OF EXCAVATION

No consideration will be given to the nature of the materials, and all excavation will be designated as unclassified excavation.

1.8 BLASTING

Blasting will not be permitted.

1.9 UTILIZATION OF EXCAVATED MATERIALS

Unsatisfactory materials removed from excavations shall be disposed of in designated waste disposal or spoil areas. Satisfactory material removed from excavations shall be used, insofar as practicable, in the construction

of fills, embankments, and subgrades. No satisfactory excavated material shall be wasted without specific written authorization. Satisfactory material authorized to be wasted shall be disposed of in designated areas approved for surplus material storage or designated waste areas as directed. No excavated material shall be disposed of to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 STRIPPING OF TOPSOIL

Where indicated or directed, topsoil shall be stripped to a depth of 6 inches. Topsoil shall be spread on areas already graded and prepared for topsoil, or transported and deposited in stockpiles convenient to areas that are to receive application of the topsoil later, or at locations indicated or specified. Topsoil shall be kept separate from other excavated materials, brush, litter, objectionable weeds, roots, stones larger than 2 inches in diameter, and other materials that would interfere with planting and maintenance operations. Any surplus of topsoil from excavations and grading shall be removed from the site.

3.2 GENERAL EXCAVATION

The Contractor shall perform excavation of every type of material encountered within the limits of the project to the lines, grades, and elevations indicated and as specified. Grading shall be in conformity with the typical sections shown and the tolerances specified in paragraph FINISHING. Satisfactory excavated materials shall be transported to and placed in fill or embankment within the limits of the work. Unsatisfactory materials encountered within the limits of the work shall be excavated below grade and replaced with satisfactory materials as directed. Such excavated material and the satisfactory material ordered as replacement shall be included in excavation. Surplus satisfactory excavated material not required for fill or embankment shall be disposed of in areas approved for surplus material storage or designated waste areas. Unsatisfactory excavated material shall be disposed of in designated waste or spoil areas.

During construction, excavation and fill shall be performed in a manner and sequence that will provide proper drainage at all times. Material required for fill or embankment in excess of that produced by excavation within the grading limits shall be excavated from the borrow areas indicated or from other approved areas selected by the Contractor as specified.

3.2.1 Channels

Excavation of channels shall be accomplished by cutting accurately to the cross sections, grades, and elevations shown. Channels shall not be excavated below grades shown. Excessive channel excavation shall be backfilled with satisfactory, thoroughly compacted, material to grades shown. Material excavated shall be disposed of as shown or as directed,

except that in no case shall material be deposited less than 4 feet from the edge of the channel. The Contractor shall maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work. Prior to concrete placement, the channel subgrade shall be thoroughly checked for unstable areas by probing the surface with a number-4 reinforcing bar; unstable surfaces shall be stabilized prior to steel and concrete placement.

3.2.2 Drainage Structures

Excavations shall be made to the lines, grades, and elevations shown, or as directed. Trenches and foundation pits shall be of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. When concrete or masonry is to be placed in an excavated area, the bottom of the excavation shall not be disturbed. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.3 SELECTION OF BORROW MATERIAL

Borrow material may be satisfactory materials for use as general earthwork or levee reconstruction. Borrow material shall be obtained from the borrow areas shown on drawings (such as the Ella Road Borrow Site provided that satisfactory materials are encountered at that site) or from other approved private sources. Unless otherwise provided in the contract, the Contractor shall obtain from the owners the right to procure material, pay royalties and other charges involved, and bear the expense of developing the sources, including rights-of-way for hauling. Borrow material from approved sources on Government-controlled land may be obtained without payment of royalties.

Unless specifically provided, no borrow shall be obtained within the limits of the project site without prior written approval. Necessary clearing, grubbing, and satisfactory drainage of borrow pits and the disposal of debris thereon shall be considered related operations to the borrow excavation.

3.4 OPENING AND DRAINAGE OF EXCAVATION AND BORROW PITS

The Contractor shall notify the Contracting Officer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, borrow pits and other excavation areas shall be excavated providing adequate drainage. Overburden and other spoil material shall be transported to designated spoil areas or otherwise disposed of as directed. Borrow pits shall be neatly trimmed and drained after the excavation is completed. The Contractor shall ensure that excavation of any area, operation of borrow pits, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

3.5 BACKFILL

Backfill adjacent to any and all types of structures shall be placed and compacted to at least 90 percent laboratory maximum dry density for general earthwork materials or 95 percent laboratory maximum dry density for levee reconstruction materials and subgrades. Materials shall be placed and

compacted in such a manner as to prevent wedging action or eccentric loading upon or against structures. Ground surface on which backfill is to be placed shall be prepared as specified in paragraph PREPARATION OF GROUND SURFACE FOR EMBANKMENTS. Compaction requirements for backfill materials shall also conform to the applicable portions of paragraphs PREPARATION OF GROUND SURFACE FOR EMBANKMENTS, EMBANKMENTS, and SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.6 PREPARATION OF GROUND SURFACE FOR EMBANKMENTS

3.6.1 General Requirements

Ground surface on which fill is to be placed shall be stripped of live, dead, or decayed vegetation, rubbish, debris, and other unsatisfactory material; plowed, disked, or otherwise broken up to a depth of 1-foot; pulverized; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent of the laboratory maximum dry density. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. The prepared ground surface shall be scarified and moistened or aerated as required just prior to placement of general earthwork or levee reconstruction materials to assure adequate bond between the material and the prepared ground surface.

3.7 EMBANKMENTS

3.7.1 Levee Reconstruction

Levee reconstruction shall not commence until all construction within the prismatic section of the levee is complete, tested, and approved. Levees shall be reconstructed from levee reconstruction materials. The material shall be placed in successive horizontal layers of loose material not more than 8 inches in depth. Each layer shall be spread uniformly on a soil surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, each layer shall be plowed, disked, or otherwise broken up; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 95 percent laboratory maximum dry density. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements shall be identical with those requirements specified in paragraph SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.7.2 General Earthwork

General Earthwork for stability berms and seepage berms shall not commence until the drainage layer has been constructed and approved as specified in Section 02714a DRAINAGE LAYER and wrapped in filter fabric as specified in Section 02738a GEOTEXTILES USED AS FILTERS. General earthwork material shall be placed in successive horizontal layers of loose material not more than 8 inches in depth. Each layer shall be spread uniformly on a soil

surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, each layer shall be plowed, disked, or otherwise broken up; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent laboratory maximum dry density. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements shall be identical with those requirements specified in paragraph SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.8 SUBGRADES

3.8.1 Construction

Subgrades for maintenance roads and the reconstructed levee crest shall be shaped to line, grade, and cross section, and compacted as specified. This operation shall include plowing, diskings, and any moistening or aerating required to obtain specified compaction. Unstable or otherwise unsatisfactory material shall be removed and replaced with satisfactory material or bridging material as directed. Low areas resulting from removal of unsatisfactory material shall be brought up to required grade with satisfactory materials, and the entire subgrade shall be shaped to line, grade, and cross section and compacted as specified. After rolling, the surface of the subgrade for roadways shall not show deviations greater than 1 inches when tested with a 10-foot straightedge applied both parallel and at right angles to the centerline of the area. The elevation of the finish subgrade shall not vary more than 0.05 foot from the established grade and cross section.

3.8.2 Compaction

Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Each layer of the embankment shall be compacted to at least 95 percent of laboratory maximum dry density for a minimum depth of 12 inches.

3.9 FINISHING

The surface of excavations, embankments, and subgrades shall be finished to a smooth and compact surface in accordance with the lines, grades, and cross sections or elevations shown. The degree of finish for graded areas shall be within 0.1 foot of the grades and elevations indicated except that the degree of finish for subgrades shall be specified in paragraph SUBGRADE PREPARATION. Gutters and ditches shall be finished in a manner that will result in effective drainage. The surface of areas to be topsoiled shall be finished to a smoothness suitable for the application of revegetation materials.

3.10 TESTING

Testing shall be performed by an approved independent commercial testing laboratory approve by the Contracting Officer. See Section 01451 for additional requirements. If the Contractor elects to establish testing facilities, no work requiring testing will be permitted

until the Contractor's facilities have been inspected and approved by the Contracting Officer. Field in-place dry density shall be determined in accordance with ASTM D 1556 and/or ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked and adjusted using only the sand cone method as described in ASTM D 1556. ASTM D 2922 results in a wet unit weight of soil and when using this method ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017; the calibration checks of both the density and moisture gauges shall be made at the beginning of a job on each different type of material encountered and at intervals of one ASTM D 1556 sand cone check test for each set of five ASTM D 2922 nuclear density tests unless otherwise directed by the Contracting Officer. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, the material shall be removed, replaced and recompacted to meet specification requirements. Tests on recompacted areas shall be performed to determine conformance with specification requirements. Inspections and test results shall be certified by a registered professional civil engineer. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that the results are representative of the materials or conditions being certified by the tests. The following number of tests, if performed at the appropriate time, will be the minimum acceptable for each type operation.

3.10.1 Fill and Backfill Material Gradation

One test per 1000 cubic yards stockpiled or in-place source material. Gradation of fill and backfill material shall be determined in accordance with ASTM D 422.

3.10.2 In-Place Densities

- a. One test per 10,000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines.
- b. One test per 1000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by hand-operated machines.
- c. One test per 100 linear feet, or fraction thereof, of each lift of levee reconstruction or excavated drainage channel subgrade.

3.10.3 Check Tests on In-Place Densities

If ASTM D 2922 is used, in-place densities shall be checked by ASTM D 1556 as follows:

- a. One check test per lift for each 50,000 square feet, or fraction thereof, of each lift of fill or backfill compacted by other than hand-operated machines.
- b. One check test per lift for each 5,000 square feet, of fill or backfill areas compacted by hand-operated machines.

- c. One check test per lift for each 500 linear feet, or fraction thereof, of levee reconstruction or excavated drainage channel subgrade.

3.10.4 Moisture Contents

In the stockpile, excavation, or borrow areas, a minimum of two tests per day per type of material or source of material being placed during stable weather conditions shall be performed. During unstable weather, tests shall be made as dictated by local conditions and approved by the Contracting Officer.

3.10.5 Optimum Moisture and Laboratory Maximum Density

Tests shall be made for each type material or source of material to determine the optimum moisture and laboratory maximum density values. One representative test per 5,000 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density.

3.10.6 Tolerance Tests for Subgrades

Continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION shall be made during construction of the subgrades.

3.11 SUBGRADE AND EMBANKMENT PROTECTION

During construction, embankments and excavations shall be kept shaped and drained. Ditches and drains along subgrade shall be maintained to drain effectively at all times. The finished subgrade shall not be disturbed by traffic or other operation and shall be protected and maintained by the Contractor in a satisfactory condition until crushed rock is placed. The storage or stockpiling of materials on the finished subgrade will not be permitted. No crushed rock shall be placed until the subgrade has been checked and approved, and in no case shall crushed rock be placed on a unstable subgrade.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02300A (PUMP STATION)

EARTHWORK

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 MEASUREMENT
 - 1.2.1 Excavation
- 1.3 PAYMENT
 - 1.3.1 Classified Excavation
 - 1.3.2 Unclassified Excavation
- 1.4 DEFINITIONS
 - 1.4.1 Satisfactory Materials
 - 1.4.2 Unsatisfactory Materials
 - 1.4.3 Degree of Compaction
- 1.5 SUBMITTALS
- 1.6 SUBSURFACE DATA
- 1.7 CLASSIFICATION OF EXCAVATION
 - 1.7.1 Common Excavation
- 1.8 BLASTING
- 1.9 UTILIZATION OF EXCAVATED MATERIALS

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 STRIPPING OF TOPSOIL
- 3.2 GENERAL EXCAVATION
 - 3.2.1 Ditches, or Gutters.
 - 3.2.2 Drainage Structures
- 3.3 OPENING AND DRAINAGE OF EXCAVATION
- 3.4 GRADING AREAS
- 3.5 BACKFILL
- 3.6 PREPARATION OF GROUND SURFACE FOR EMBANKMENTS
 - 3.6.1 General Requirements
- 3.7 EMBANKMENTS
 - 3.7.1 Earth Embankments
- 3.8 SUBGRADE PREPARATION
 - 3.8.1 Construction
 - 3.8.2 Compaction
- 3.9 FINISHING
- 3.10 TESTING
 - 3.10.1 Fill and Backfill Material Gradation
 - 3.10.2 In-Place Densities
 - 3.10.3 Check Tests on In-Place Densities

- 3.10.4 Moisture Contents
- 3.10.5 Optimum Moisture and Laboratory Maximum Density
- 3.10.6 Tolerance Tests for Subgrades

-- End of Section Table of Contents --

SECTION 02300A

EARTHWORK (PUMP STATION)

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
(AASHTO)

AASHTO T 180 (1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop

AASHTO T 224 (1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136 (1996a) Sieve Analysis of Fine and Coarse Aggregates

ASTM C 117 Gradation tests

ASTM D 1140 (1997) Amount of Material in Soils Finer than the No. 200 (75-micrometer) Sieve

ASTM D 1556 (1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method

ASTM D 1557 (1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))

ASTM D 2167 (1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method

ASTM D 2487 (1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)

ASTM D 2937 (1994) Density of Soil in Place by the

Drive-Cylinder Method

ASTM D 3017 (1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

ASTM D 4318 (1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils

1.2 MEASUREMENT

1.2.1 Excavation

The unit of measurement for excavation will be the cubic yard, computed by the average end area method from cross sections taken before and after the excavation operations. The volume to be paid for will be the number of cubic yards of material measured in its original position and removed from the excavation areas, including the excavation for ditches, or gutters, when the material is acceptably utilized or disposed of as herein specified. The measurements will include authorized excavation of rock, authorized excavation of unsatisfactory subgrade soil, and the volume of loose, scattered rocks and boulders collected within the limits of the work; allowance will be made on the same basis for selected backfill ordered as replacement. The measurement will not include the volume of subgrade material or other material that is scarified or plowed and reused in-place, and will not include the volume excavated without authorization or the volume of any material used for purposes other than directed. The measurement will not include the volume of any excavation performed prior to the taking of elevations and measurements of the undisturbed grade.

1.3 PAYMENT

Payment will constitute full compensation for all labor, equipment, tools, supplies, and incidentals necessary to complete the work.

1.3.1 Classified Excavation

Classified excavation will be paid for at the contract unit prices per cubic yard for common or rock excavation.

1.3.2 Unclassified Excavation

Unclassified excavation will be paid for at the contract unit price per cubic yard for unclassified excavation.

1.4 DEFINITIONS

1.4.1 Satisfactory Materials

Satisfactory materials shall comprise any materials classified by ASTM D 2487 as GW, GP, GM, GP-GM, GW-GM, GC, GP-GC, GM-GC, SW, SP, . Satisfactory materials for grading shall be comprised of stones less than 3 inches in any dimension.

1.4.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills; trash; refuse; backfills from previous construction; and material classified as satisfactory which contains root and other organic matter or frozen material. The Contracting Officer shall be notified of any contaminated materials.

1.4.3 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 3/4 inch sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 3/4 inch sieve shall be expressed as a percentage of the maximum density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Earthwork; .

Procedure and location for disposal of unused satisfactory material.
Blasting plan when blasting is permitted.

SD-06 Test Reports

Testing; .

Within 24 hours of conclusion of physical tests, Two copies of test results, including calibration curves and results of calibration tests.

SD-07 Certificates

Testing; .

Qualifications of the commercial testing laboratory or Contractor's testing facilities.

1.6 SUBSURFACE DATA

No subsurface soil information is available for the project site. Materials in cut banks may be unyielding or contain rock that will require ripping and excavation by large trackhoe sized equipment; no additional compensation shall be forthcoming for extra construction effort to excavate rock and unyielding materials.

1.7 CLASSIFICATION OF EXCAVATION

Excavation specified shall be done on a classified basis, in accordance with the following designations and classifications. Materials in the cut banks may be unyielding or contain rock that will require ripping and excavation by large trackhoe sized equipment; no additional compensation shall be forthcoming for extra excavation effort to excavate rock and unyielding materials.

1.7.1 Common Excavation

Common excavation shall include the satisfactory removal and disposal of all materials not classified as rock excavation.

1.8 BLASTING

Blasting will not be permitted.

1.9 UTILIZATION OF EXCAVATED MATERIALS

Unsatisfactory materials removed from excavations shall be disposed of in designated waste disposal or spoil areas. Satisfactory material removed from excavations shall be used, insofar as practicable, in the construction of fills, embankments, subgrades, shoulders, bedding (as backfill), and for similar purposes. No satisfactory excavated material shall be wasted without specific written authorization. Satisfactory material authorized to be wasted shall be disposed of in designated areas approved for surplus material storage or designated waste areas as directed. Newly designated waste areas on Government-controlled land shall be cleared and grubbed before disposal of waste material thereon. Coarse rock from excavations shall be stockpiled and used for constructing slopes or embankments adjacent to streams, or sides and bottoms of channels and for protecting against erosion. No excavated material shall be disposed of to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 STRIPPING OF TOPSOIL

Where indicated or directed, topsoil shall be stripped to a depth of six (6) inches. Topsoil shall be spread on areas already graded and prepared for topsoil, or transported and deposited in stockpiles convenient to areas that are to receive application of the topsoil later, or at locations

indicated or specified. Topsoil shall be kept separate from other excavated materials, brush, litter, objectionable weeds, roots, stones larger than 2 inches in diameter, and other materials that would interfere with planting and maintenance operations. Any surplus of topsoil from excavations and grading shall be stockpiled in locations indicated .

3.2 GENERAL EXCAVATION

The Contractor shall perform excavation of every type of material encountered within the limits of the project to the lines, grades, and elevations indicated and as specified. Grading shall be in conformity with the typical sections shown and the tolerances specified in paragraph FINISHING. Satisfactory excavated materials shall be transported to and placed in fill or embankment within the limits of the work. Unsatisfactory materials encountered within the limits of the work shall be excavated below grade and replaced with satisfactory materials as directed. Such excavated material and the satisfactory material ordered as replacement shall be included in excavation. Surplus satisfactory excavated material not required for fill or embankment shall be disposed of in areas approved for surplus material storage or designated waste areas. Unsatisfactory excavated material shall be disposed of in designated waste or spoil areas.

During construction, excavation and fill shall be performed in a manner and sequence that will provide proper drainage at all times. Material required for fill or embankment in excess of that produced by excavation within the grading limits shall be excavated from other approved areas selected by the Contractor as specified.

3.2.1 Ditches, or Gutters.

Excavation of ditches, or gutters. shall be accomplished by cutting accurately to the cross sections, grades, and elevations shown. Ditches and gutters shall not be excavated below grades shown. Excessive open ditch or gutter excavation shall be backfilled with satisfactory, thoroughly compacted, material or with suitable stone or cobble to grades shown. Material excavated shall be disposed of as shown or as directed, except that in no case shall material be deposited less than 4 feet from the edge of a ditch. The Contractor shall maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work.

3.2.2 Drainage Structures

Excavations shall be made to the lines, grades, and elevations shown, or as directed. Trenches and foundation pits shall be of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. Rock or other hard foundation material shall be cleaned of loose debris and cut to a firm, level, stepped, or serrated surface. Loose disintegrated rock and thin strata shall be removed. When concrete or masonry is to be placed in an excavated area, the bottom of the excavation shall not be disturbed. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed. Where pile foundations are to be used, the excavation of each pit shall be stopped at an elevation 1 foot above the base of the footing, as specified, before piles are driven. After the pile

driving has been completed, loose and displaced material shall be removed and excavation completed, leaving a smooth, solid, undisturbed surface to receive the concrete or masonry.

3.3 OPENING AND DRAINAGE OF EXCAVATION

The Contractor shall notify the Contracting Officer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, excavation areas shall be excavated providing adequate drainage. Overburden and other spoil material shall be transported to designated spoil areas or otherwise disposed of as directed. The Contractor shall ensure that excavation of any area, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

3.4 GRADING AREAS

Where indicated, work will be divided into grading areas within which satisfactory excavated material shall be placed in embankments, fills, and required backfills. The Contractor shall not haul satisfactory material excavated in one grading area to another grading area except when so directed in writing.

3.5 BACKFILL

Backfill adjacent to any and all types of structures shall be placed and compacted to at least 90 percent laboratory maximum density for cohesive materials to prevent wedging action or eccentric loading upon or against the structure. Ground surface on which backfill is to be placed shall be prepared as specified in paragraph PREPARATION OF GROUND SURFACE FOR EMBANKMENTS. Compaction requirements for backfill materials shall also conform to the applicable portions of paragraphs PREPARATION OF GROUND SURFACE FOR EMBANKMENTS, EMBANKMENTS, and SUBGRADE PREPARATION, and Section 02630 STORM-DRAINAGE SYSTEM; and Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.6 PREPARATION OF GROUND SURFACE FOR EMBANKMENTS

3.6.1 General Requirements

Ground surface on which fill is to be placed shall be stripped of live, dead, or decayed vegetation, rubbish, debris, and other unsatisfactory material; plowed, disked, or otherwise broken up to a depth of eight (8); pulverized; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent laboratory maximum density for cohesive materials. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. The prepared ground surface shall be scarified and moistened or aerated as required just prior to placement of embankment materials to assure adequate bond between embankment material and the prepared ground surface, and compaction of the earth fill shall not in any

way damage the filter fabric or drainage layer.

3.7 EMBANKMENTS

3.7.1 Earth Embankments

Earth embankments shall be constructed from satisfactory materials free of organic or frozen material and rocks with any dimension greater than 3 inches. The material shall be placed in successive horizontal layers of loose material not more than eight (8) inches in depth. Each layer shall be spread uniformly on a soil surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, each layer shall be plowed, disked, or otherwise broken up; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent laboratory maximum density for cohesive materials. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements shall be identical with those requirements specified in paragraph SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.8 SUBGRADE PREPARATION

3.8.1 Construction

Subgrade shall be shaped to line, grade, and cross section, and compacted as specified. This operation shall include plowing, disking, and any moistening or aerating required to obtain specified compaction. Soft or otherwise unsatisfactory material shall be removed and replaced with satisfactory excavated material or other approved material as directed. Rock encountered in the cut section shall be excavated to a depth of 6 inches below finished grade for the subgrade. Low areas resulting from removal of unsatisfactory material or excavation of rock shall be brought up to required grade with satisfactory materials, and the entire subgrade shall be shaped to line, grade, and cross section and compacted as specified. After rolling, the surface of the subgrade for roadways shall not show deviations greater than one-half ($\frac{1}{2}$) inch when tested with a eight (8) foot straightedge applied both parallel and at right angles to the centerline of the area. The elevation of the finish subgrade shall not vary more than 0.05 foot from the established grade and cross section.

3.8.2 Compaction

Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Except for paved areas and railroads, each layer of the embankment shall be compacted to at least ninety(90) percent of laboratory maximum density.

3.9 FINISHING

The surface of excavations, embankments, and subgrades shall be finished to a smooth and compact surface in accordance with the lines, grades, and

cross sections or elevations shown. The degree of finish for graded areas shall be within 0.1 foot of the grades and elevations indicated except that the degree of finish for subgrades shall be specified in paragraph SUBGRADE PREPARATION. Gutters and ditches shall be finished in a manner that will result in effective drainage. The surface of areas to be turfed shall be finished to a smoothness suitable for the application of turfing materials.

3.10 TESTING

Testing shall be performed by an approved commercial testing laboratory or by the Contractor subject to approval. If the Contractor elects to establish testing facilities, no work requiring testing will be permitted until the Contractor's facilities have been inspected and approved by the Contracting Officer. Field in-place density shall be determined in accordance with ASTM C 117 and ASTM C136 . When ASTM D is used, the calibration curves shall be checked and adjusted using only the sand cone method as described in ASTM D 1556. results in a wet unit weight of soil and when using this method ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017; the calibration checks of both the density and moisture gauges shall be made at the beginning of a job on each different type of material encountered and at intervals as directed by the Contracting Officer. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, the material shall be removed, replaced and recompactd to meet specification requirements. Tests on recompactd areas shall be performed to determine conformance with specification requirements. Inspections and test results shall be certified by a registered professional civil engineer. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that the results are representative of the materials or conditions being certified by the tests.

The following number of tests, if performed at the appropriate time, will be the minimum acceptable for each type operation.

3.10.1 Fill and Backfill Material Gradation

One test per 1,000 cubic yards stockpiled or in-place source material. Gradation of fill and backfill material shall be determined in accordance with ASTM C 117 and C 136 .

3.10.2 In-Place Densities

- a. One test per 5,000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines.
- b. One test per 1,000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by hand-operated machines.
- c. One test per 500 linear feet, or fraction thereof, of each lift of embankment or backfill for roads .

3.10.3 Check Tests on In-Place Densities

In-place densities shall be checked by ASTM D 1556 as follows:

- a. One check test per lift for each 20,000 square feet, or fraction thereof, of each lift of fill or backfill compacted by other than hand-operated machines.
- b. One check test per lift for each 5,000 square feet, of fill or backfill areas compacted by hand-operated machines.
- c. One check test per lift for each 1,000 linear feet, or fraction thereof, of embankment or backfill for roads .

3.10.4 Moisture Contents

In the stockpile, excavation, or borrow areas, a minimum of two tests per day per type of material or source of material being placed during stable weather conditions shall be performed. During unstable weather, tests shall be made as dictated by local conditions and approved by the Contracting Officer.

3.10.5 Optimum Moisture and Laboratory Maximum Density

Tests shall be made for each type material or source of material including borrow material to determine the optimum moisture and laboratory maximum density values. One representative test per 5,000 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density.

3.10.6 Tolerance Tests for Subgrades

Continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION shall be made during construction of the subgrades.

-- End of Section --